




- NOTES :
- THE FOLLOWING INFORMATION IS OBTAINED FROM THE PROJECT DESIGN DRAWINGS:
 - POLE LENGTH AND STRENGTH.
 - SPECIAL FOUNDATION REQUIREMENTS.
 - POLE EMBEDMENT DEPTH.
 - CONDUCTOR SIZE.
 - CROSSARM SIZE AND BRACE REQUIREMENTS.
 - STAY REQUIREMENTS.
 - DEVIATION ANGLE.
 - THE MAXIMUM LINE DEVIATION ANGLE TO BE CONSTRUCTED ON THIS ARRANGEMENT IS TO BE DETERMINED BY THE LINE DESIGNER.
 - ALL BOLTS AND INSULATOR PINS PASSING THROUGH TIMBER ARE TO BE COATED WITH GRAPHITE GREASE.
 - POLES SHALL BE DRILLED, SCARFED AND DRESSED ON SITE. DRILLING AND SCARFING TO BE TREATED WITH APPROVED PRESERVATIVES.
 - NON-TENSION COMPRESSION SLEEVES TO BE USED WHEN REQUIRED TO JOIN CONDUCTORS.
 - THE SHACKLE STRAP IS TO BE FORMED TO SUIT THE CROSSARM AND INSULATOR.
 - REFER TO DRG: 514044 FOR DETAILS OF A SUITABLE CONDUCTOR TIE ARRANGEMENT FOR CONNECTION OF THE TAPPING CONDUCTOR TO THE LV PIN INSULATOR.
 - A 2700mm CROSSARM IS TO BE USED AS THE DEFAULT CROSSARM. FOR NARROW FEEDER ALIGNMENTS, A 2400mm CROSSARM MAY BE CONSIDERED TO OVERCOME DESIGN AND SITE CONSTRAINTS.
 - ONLY THE 2700mm CROSSARM OPTION IS SHOWN ON THIS CONSTRUCTION DRAWING. REFER TO DRG: 15233 FOR DRILLING PATTERN OF 2400mm CROSSARM. ADDITIONAL Ø18mm HOLES WILL BE REQUIRED TO BE DRILLED IN THE TOP OF THE CROSSARM 150mm FROM THE PHASE CONDUCTOR ATTACHMENT LOCATIONS TO MOUNT THE LV FUSE BASES.
 - THE 690mm CROSSARM BRACES ARE TO BE USED ON A 2700mm CROSSARM.
THE 490mm CROSSARM BRACES ARE TO BE USED ON A 2400mm CROSSARM.
 - THE LV FUSE RATING IS TO BE DETERMINED BY THE LINE DESIGNER WITH REFERENCE TO AUSGRID'S TECHNICAL GUIDE T0024 - TS4200 FUSE STANDARD.
 - POLE STEPS ARE TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF NS128.
 - REFER TO DESIGNER SAFETY REPORT D25/188962 FOR ATYPICAL HAZARDS ASSOCIATED WITH THIS STANDARD CONSTRUCTION.

31	STEP - POLE, SCREW-IN (SEE NOTE 12)	250144	185198	A/R
30	FUSE - HRC, 415V, 2 HOLE BOLT-IN (111mm FIXING CENTRES) (SEE NOTE 11)			3
29	WASHER - SQUARE, 50x50x6mm, GALVANISED (Ø18mm HOLE)	518081	H39257	3
28	NUT - M12, HEX., STAINLESS STEEL	515467	8987	6
27	WASHER - SPRING, M12, STAINLESS STEEL	518082	143859	6
26	WASHER - FLAT, M12, STAINLESS STEEL	518081	49429	12
25	BOLT - M12x40mm, HEX., STAINLESS STEEL	515467	45146	6
24	LUG - M12, COMPRESSION (TO SUIT CONDUCTOR)	514053		6
23	BASE & CARRIER - FUSE, LV, 630A, SINGLE CIRCUIT	117077	90522	3
22	JOINT - NON TENSION, COMPRESSION (TO SUIT CONDUCTOR) (SEE NOTE 5)	514053		1
21	TIE - CONDUCTOR, LOW VOLTAGE, SUPPORT ARRANGEMENT (SEE NOTE 7)	514044		1m
20	INSULATOR - LV, (LPLV PATTERN 'B') & PIN ARRANGEMENT	513995		1
19	DEADEND - PREFORMED, HELICAL (TO SUIT CONDUCTOR)	514098		8
18	BOLT & NUT - M16x130mm, HEX., GALVANISED	515466	46979	8
17	INSULATOR - SHACKLE, REEL, TYPE SH.LV2	514407	75812	8
16	BRACKET - MOUNTING, SHACKLE, LV FLAT, GALVANISED (SEE NOTE 6)	514379	H17762	16
15	WASHER - FLAT, M16, GALVANISED	518081	177984	9
14	WASHER - CONICAL, M16, GALVANISED	518082	H39647	6
13	BOLT & NUT - M16x150mm, HEX., GALVANISED	515466	175672	6
12	BLOCK - GAIN, ALUMINIUM, 100mm		146274	1
11	WASHER - FLAT, M20, GALVANISED	518081	177986	1
10	WASHER - CONICAL, M20, GALVANISED	518082	H39655	1
9	WASHER - SQUARE, 75x75x6mm, GALVANISED (Ø22mm HOLE)	518081	H39231	2
8	BOLT & NUT - M20, HEX., GALVANISED (LENGTH TO SUIT POLE)	515466		1
7	WASHER - CONICAL, M12, GALVANISED	518082	H39639	2
6	WASHER - FLAT, M12, GALVANISED	518081	177982	4
5	BOLT & NUT - M12x150mm, HEX., GALVANISED (USE WITH 2400mm CROSSARM)	515466	46847	2
	BOLT & NUT - M12x180mm, HEX., GALVANISED (USE WITH 2700mm CROSSARM)	515466	46888	
4	CROSSARM - 2400x125x100mm, TYPE LT3, HARDWOOD (SEE NOTES 8 & 9)	15233	71746	1
	CROSSARM - 2700x150x100mm, TYPE F, HARDWOOD (SEE NOTES 8 & 9)	514373	H23892	
3	SCREW - COACH, M12 x 100mm, GALVANISED		H40484	1
2	BRACE - CROSSARM, FLAT, TYPE L, 490mm, GALVANISED (SEE NOTE 10)	46	76745	2
	BRACE - CROSSARM, FLAT, 690mm, GALVANISED (SEE NOTE 10)	514385	H17738	
1	POLE - TIMBER (AS REQUIRED)	513988		1

ITEM	DESCRIPTION	DRG. No	STOCK CODE	QTY
SCALE	1:15	STANDARD CONSTRUCTION LV THROUGH MAINS TERMINATION CONSTRUCTION WITH LV FUSES 1-60		
DESIGNED	P.JONES			
DRAWN	P.RIOS			
CHECKED	C.ROSKELL			
APPROVED	G.FORD			
DATE	12/08/2025			
PROJECT NUMBER	STD			
TRIM REF NUMBER	-	SIZE A2	DRAWING No 271397	SHEET 1
			REV 0	

CAD DRAWING DO NOT MANUALLY AMEND AMENDMENTS					
	LV CONDUCTOR TIE & SUPPORT ARRANGEMENTS	514044			
	WOODEN CROSSARMS FOR 415V OVERHEAD MAINS	15233			
ASSOCIATED DRAWINGS					

NETWORK STANDARD



42 HONEYSUCKLE DRIVE,
NEWCASTLE WEST NSW 2300