
# Underground CONSAC cable installation



### **Construction stages**

### Trenching and conduit installation

- Trenching can occur at more than one site on a project simultaneously.
- Plastic conduits (pipes) will then be placed in the trenches and then the area is backfilled.
- Then the section of road reserve is either permanently reinstated immediately or at the end of the project, depending on contractual agreements.



Time it takes to complete work outside most properties.



#### Cable installation

- At a later date, cable drums will be set up at joint bay locations.
- The new cables are pulled through the pipes and connected at the joint bays.

### 1 week

Time it takes to complete work outside most properties.



#### Cable connection

- When all the replacement cables are installed, we will connect the new cables to the pillars and your property.
- This work will involve interruptions to your power supply to allow the work to be completed safely.

## 1-2 days

Time it takes to complete work outside most properties.



